



















SHIPPING AND SITE PREPARATION

SHIPPING

MST turnstiles are shipped in five main sections: the top channel, the yoke, the roto, the OV and the yoke guard plate.

SITE PREPARATION

All turnstiles must be installed on a firm foundation in a manner that allows the required power and activation signal cabling to be pulled into the top channel. Optional conduit may be run through the OV base. The recommended slab platform is 72" square by 4" deep, level concrete. Concrete anchors, bolts and washers are included with each turnstile. Installation should be performed by a skilled installer following the manufacturer's directions and instructions. Detailed drawings and installation manuals are available online. For ease of installation and maintenance, a minimum 3" header clearance is recommended.

125 E. Stansifer Ave

Clarksville, IN 47129

Dimensions are shown in inches (mm). All measurements are approximate.



